

**SECTION 04400– STONE**  
**CONSTRUCTION STANDARD**

---

**PART 1: GENERAL**

1.01 Scope of Standard

- A. This standard provides general guidance concerning the specific preferences of the University of Texas at Austin for natural and cut stone.
- B. UT recognizes that project conditions and requirements vary, thus precluding the absolute adherence to the items identified herein in all cases. However, unless there is adequate written justification, it is expected that these guidelines will govern the design and specifications for UT projects.

1.02 Reference Standards

- A. Refer to the UT Campus Master Plan for guidelines pertaining to use of stone. Successful maintenance guidelines shall be developed and approved of prior to the specification or installation of any porous stone. Use caution when specifying use of shellstone limestone at locations where it is exposed to rainfall.
- B. Coordinate with UT Statuary conservator where applicable.
- C. Marble and Stone Slab Veneer, (Second Edition), Masonry Institute of America.
- D. Dimension Stone Design Manual, Marble Institute of America.
- E. ILI Handbook, Indiana Limestone Institute.

1.03 Quality Control

- A. Details for installation, and cleaning shall be approved by the UT project representative prior to specification or installation of any porous stone.

**PART 2: PRODUCTS**

2.01 Stone

- A. Limestone: Cordova cream limestone saw cut, Texas Quarries or equal as approved by UT project representative.
- B. Granite: Sierra white, Cold Spring Granite Co., or equal as approved by UT project representative.
- C. Anchors: Use only stainless steel.

**SECTION 04400– STONE  
CONSTRUCTION STANDARD**

---

**PART 3: EXECUTION**

3.01 General

- A. Provide drips where stone projects more than one inch.
- B. Avoid using cordova cream limestone where it extends below finished grade at lawn or planting beds.
- C. Provide masonry mock up for approval at least three months prior to needing stone on site.

END OF STANDARD 04400